

Table of Quantities
Oak Hill Road over Meadow Brook
Culvert Removal/Bridge Replacement
Enfield, New Hampshire

	Item Description	Units	Quantity	Unit Price	Total Cost
EARTHWORK					
1	Clearing & Grubbing	SF	4000		
2	Common Excavation	CY	80		
3	Rehandling Excavated Material	CY	25		
4	Unclassified Channel Excavation	CY	50		
5	Granular Backfill (Bridge)	CY	125		
6	Fine Grading	LS	1		
7	Other (Describe, If Needed)				
8	Other (Describe, If Needed)				
BASE COURSES					
9	Gravel	CY	600		
10	Crushed Gravel	CY	450		
11	Crushed Aggregate for Shoulders	CY	75		
12	Crushed Stone	CY	25		
13	Other (Describe, If Needed)				
14	Other (Describe, If Needed)				
STRUCTURES					
15	Removal of Existing Bridge Structure	EA	1		
16	Cofferdams	EA	1		
17	Common Bridge Excavation	CY	50		
18	Abutments	EA	2		
19	Guardrail (Inclusive of All Appurtenances)	EA	1		
20	Stone Fill, Class B	CY	75		
21	Stone Fill, Class C	CY	50		
22	Superstructure	EA	1		
23	Other (Describe, If Needed)				
24	Other (Describe, If Needed)				
INCIDENTAL CONSTRUCTION					
25	Loam	CY	25		
26	Dewatering	LS	1		
27	Mobilization & Demobilization	LS	1		
28	Temporary Erosion Control	LS	1		
29	Incidentals	LS	1		
30	Contingency	LS	1		
31	Bid Bond	LS	1		
32	Payment Bond	LS	1		
33	Performance Bond	LS	1		
34	Other (Describe, If Needed)				
35	Other (Describe, If Needed)				
TOTAL ESTIMATED PRICE =					

Prepared by:

Right Angle Engineering, PLLC
Erin Darrow, P.E.

Sheet 1 of 1
1/18/2022

Prepared for:
Town of Enfield, NH